



भारतीय प्रबंध संस्थान इन्दौर

प्रबंध शिखर, राऊ-पीथमपुर रोड, इन्दौर – 453 556 (म.प्र.), भारत

INDIAN INSTITUTE OF MANAGEMENT INDORE

Prabandh Shikhar, Rau-Pithampur Road, Indore - 453 556 (M.P.), India

Dated: October 3, 2016

Name of Work: Construction of Interior fit out for MDP Class rooms, Faculty cabins, in the Academic block of IIM Indore - Civil & Joinery, Electrical, Audio Visual & allied works

Ref.: NIT/Project/08/2016/31 File No. 309

Corrigendum: 2

The following amendment have been made in respect of the above referred Notice Inviting e-Tender:

- i) In the corrigendum-1 wherein the Basic Price Range of the items were mentioned, the following corrections are hereby made:

BOQ Item No.	As is mentioned in the Corrigendum-1			Shall be read as	
	Name of Items	Unit	Basic Price Range Considered	Name of Items	Basic Price Range Considered
6.1	Knauf Ceiling	Sqm	Rs.1500-1700/-	Knauf Ceiling or equivalent	Rs. 1500 - 1700/-
11.1	Anutone wooden panel	sqm	Rs.6400-7000/-	Anutone wooden panel or equivalent	Rs. 6400 - 7000/-
9.08	Fundermax high pressure laminate	Sqm	Rs.46770-47000/-	Fundermax or equivalent high pressure laminate	Rs. 4350 - 4500/-
17.15	Wall paper	Sqm	Rs.4870-5000/-	Wall paper (length =30 ft, and coverage area= 50 sqft)	Rs. 4875/- per roll

- ii) In financial Bid, the complete nomenclature for item no. 10.1 under the head 'partition' shall be read as:

"Providing and fixing 75mm to 97mm gypsteel ultra stud partition which include one layer of tapered edge 12.5mm thick gyproc moisture resistant (conforming to BS 1230 part I) is screw fixed with drywall screw of 25mm centre of either side of 48MM Gypstell ultra C' stud (0.50mm thick have equal flanges of 32mm made of GI steel) which is anchored to the floor and true ceiling using suitable anchor fasteners or metal screws with nylon plugs. The centre


distance have to be suitable reinforced to support tile finish. The boards are to be fixed to the frame works with joints staggered to avoid leakages to through joints. A gypsteel fixing channel of 48mm width (0.9mm thick having two flanges of 9.5 each) has to be jointed and finished so as to have a flush look which includes filling and finishing with gyproc jointing compound, gyproc joint paper tape and two coats of drywall top coat as per drawing and direction of Engineer in charge”

iii) In financial Bid, the complete nomenclature for item no. 10.2 under the head- ‘partition’ shall be read as:

“Providing and filling glass wool in between the Gypsum partition of 75mm thickness, 24kgr/cumt fiber glass wool for acoustic insulation for partition with necessary support of 12 mm plywood to remain intact or in position in between the partition as per direction of Engineer in charge at site.”

All other conditions remain unchanged.

Dated: October 3, 2016


(V.P. Thomas)
Chief Engineer